
GOVERNMENT OF PAKISTAN PAKHTUNKHWA HIGHWAY AUTHORITY



FEASIBILITY STUDY AND DETAILED ENGINEERING DESIGN OF ADP SCHEME NO.1581/210516 FEASIBILITY STUDY, DESIGN AND CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA

TENDER DRAWINGS

FEBRUARY, 2024



NATIONAL ENGINEERING SERVICES PAKISTAN (PVT.) LIMITED.

NESPAK HOUSE 2nd Floor Attaturk Avenue, Sector G-5/2 Islamabad- Pakistan.


LIST OF DRAWINGS

Sr.No.	TITLE OF DRAWING	DRAWING No.	TOTAL NO OF SHEETS
1	LIST OF DRAWINGS AND GENERAL NOTES	SA-488/102/TD/LDG001	01
2	KEY MAP	SA-488/102/TD/KM002	01
3	SYMBOLS AND ABBREVIATIONS	SA-488/102/TD/SA003	01
4	ROUTE LOCATION PLAN	SA-488/102/TD/RLP01	01
5	TYPICAL CROSS SECTIONS	SA-488/102/TD/TC004	01
6	TRAVERSE STATION DATA	SA-488/102/TD/TS005	01
7	GENERAL ARRANGEMENT PLAN	SA-488/102/TD/GA006	01
8	TYPICAL CROSS SECTIONS AND DETAILS	SA-488/102/TD/TCD007	01
9	PRECAST PRESTRESSED GIRDER CONCRETE OUTLINE DETAILS	SA-488/102/TD/PG008~009	02
10	RETAINING WALL CONCRETE OUTLINE & REINFORCEMENT	SA-488/102/TD/RW010	01
11	TYPICAL RCC DRAIN DETAIL	SA-488/102/TD/D011	01
12	GENERAL NOTES FOR STRUCTURES	SA-488/102/TD/GNS012	01
13	REBAR SHAPE CODE	SA-488/102/TD/RS013	01
14	TYPICAL ROAD SIGN DETAILS	SA-488/102/TD/RS014~018	05
15	PAVEMENT MARKING AND ROAD STUDS	SA-488/102/TD/PMS019	01
16	METAL GUARD RAIL	SA-488/102/TD/GR020~021	02
17	DETAIL PLAN & PROFILE DRAWINGS	SA-488/102/TD/P&P1~3	03

GENERAL NOTES

- 1. ALL DIMENSIONS SHOWN ON PLAN AND PROFILE DRAWINGS ARE IN METERS WHEREAS ANGULAR MEASUREMENTS ARE IN DEGREES, MINUTES AND SECONDS (360° TO A CIRCLE).
- 2. EACH DRAWING SHALL BE READ IN CONJUNCTION WITH OTHER DRAWINGS.
- 3. GRID CO-ORDINATES AND ELEVATIONS ARE BASED ON UTM ZONE 42-N.
- 4. MINOR CHANGES IN HORIZONTAL/VERTICAL ALIGNMENT MAY BE CARRIED OUT AT SITE WITH PRIOR APPROVAL OF THE ENGINEER.
- 5. STRUCTURES SHOWN ON PLAN/PROFILE ARE SYMBOLIC. FOR DETAIL OF STRUCTURES AND PROTECTION WORKS SEE RELEVANT DRAWING. HOWEVER DETAILED INVENTORY OF STRUCTURES SHALL BE PREPARED AS PER SITE CONDITION/REQUIREMENTS AND SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO COMMENCEMENT OF CONSTRACTION ACTIVITES AT SITE.
- 6. FOR PAVEMENT MARKING AND ROAD SIGNS, CONTRACTOR SHALL SUBMIT DETAILED PLANS DRAWINGS FOR APPROVAL OF THE ENGINEER.
- 7. LOCATION OF UNDER GROUND CABLES/UTILITIES SHOWN ON PLANS ARE APPROXIMATE. EXACT LOCATION SHALL BE DETERMINED BY THE CONTRACTOR AT HIS OWN COST.
- 8. ANY DAMAGE DONE TO THE UTILITIES DURING EXCAVATION/EXECUTION OF WORKS SHALL BE IMMEDIATELY REPAIRED BY THE CONTRACTOR AT HIS OWN COST TO THE SATISFACTION OF CONCERNED DEPARTMENTS.
- 9. THE SUBGRADE MATERIAL SHALL HAVE A MINIMUM SOAKED C.B.R. OF 08% AT 95% M.D.D. AASHTO T-180 FOR BOTH FILL AND CUT SECTIONS.
- 10. THE LENGTHS, SIZES, SLOPES, INVERT LEVELS AND OTHERS GIVEN DETAILS REGARDING CULVERTS, AS SHOWN IN SCHEDULE OF STRUCTURES ARE TENTATIVE. THE CONTRACTOR SHALL PREPARE SHOP DRAWINGS OF EACH CULVERT LOCATIONS WITH THE REQUIRED SKEW ANGLE AS PER SITE REQUIREMENTS AND SHALL SUBMIT THE SAME TO THE ENGINEER FOR APPROVAL PRIOR TO CONSTRUCTION EXECUTION.
- 11. THE CONTRACTOR SHALL BE RESPONSIBLE TO CATER FOR ALL TEMPORARY TRAFFIC DIVERSIONS BEFORE START OF CONSTRUCTION OF THE ROAD TO THE CNTIRE SATISFACTION OF THE ENGINEER INCLUDING DETOUR ROAD AND ITS MAINTENANCE, SPRINKLING OF WATER, GRADING AND COMPACTION WHEN AND WHERE REQUIRED AT HIS OWN COST.
- 12. RETAINING/BREAST/TOE WALL, GUARD RAIL, CONCRETE CURB STONES, FOOTPATH, ROAD SIGNS, GANTRY SIGNS, PAVEMENT STUDS AND OTHER ANCILLARY ITEMS SHALL BE PROVIDED AS PER THE BOQ ITEMS, AS PER SITE REQUIREMENT OR AS DIRECTED BY THE ENGINEER. CONTRACTOR SHALL PREPARE THE SHOP DRAWINGS FOR EACH ACTIVITY/ LOCATION ALONG WITH METHODOLOGY AND SHALL SUBMIT FOR APPROVAL TO THE ENGINEER PRIOR TO START OF CONSTRUCTION.
- 13. TWO COATS OF BITUMEN PAINT SHALL BE APPLIED ON CONCRETE FACES IN CONTACT WITH THE SOIL. COST OF THIS ITEM IS DEEMED TO BE INCLUDED IN THE RELEVENT BOQ ITEM RATES AND NO SEPRATE PAYMENT SHALL BE MADE FOR THIS ITEM OF WORK.
- 14. RETAINING/DRAINAGE STRUCTURES FOUNDATION SHALL BE PLACED ON FIRM, HARD AND ROCKY STRATA, OR AS DIRECTED BY ENGINEER.
- 15. ROADWAY EXCAVATION MATERIAL SHELL BE UTILIZED IN MOST EFFECTIVE MANNER IN THE EMBANKMENT EVEN WITH BLENDING /MIXING WITH THE SUPERIOR MATERIALS (IF REQUIRED, WIHTOUT AT ANY EXTRA COST). ROADWAY EXCAVATION SHALL NOT BE DISPOSED OFF OUTSIDE RIGHT OF WAY, IT IS MANDATORY TO UTILIZE IN THE PROJECT.
- 16. DURING EXECUTION, JOINT CROSS SECTION AND ACTUAL NSL OF CENTER LINE WILL BE PROVIDED TO FINALIZE THE ROAD PROFILE PRIOR TO COMMONS CONSTRUCTION ACTIVELY AT SITE.





	NATIONAL	ENGINEERING	SERVICES	
- the same of the	PAKISTAN	(PVT.) LTD.		

	L				
		1//		DRAWN	
				SUBMITTED	
				RECOMMENDED	
				CHD./VER.	
REV.	DATE	DESCRIPTION	APPROVED	APPROVED	


CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA

TITLE	LIST	OF	DRA	AWINGS
	& G1	ENE	RAL	NOTES

(TE

DWG NO.

MARCH, 2022 SA-488/102/TD/LDG001




SYMBOLS

ABBREVIATIONS

TENDER DRAWINGS

NOT TO BE USED FOR CONSTRUCTION

CIRCULAR CURVE PARAMETERS



DATE










1 2 00	/	DRAWN	
NAM *		SUBMITTED	
7		RECOMMENDED	
		CHD./VER.	
DESCRIPTION	APPROVED	APPROVED	

CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA

SYMBOLS AND ABBREVIATIONS	TITLE	TITLE	SYMBOLS	AND	ABBREVIATIONS
---------------------------	-------	-------	---------	-----	---------------

N	SIMDOLS	AND ABBREVIATIONS
	DATE	DWG NO.
As is law	MARCH, 2022	SA-488/102/TD/ SA003



SUMMARY OF SURVEY CONTROL POINTS

s. NO.	Easting (m)	Northing (m)	Elevation (m)	Code	
1 759281.95		3857861.72	735.92	BM11A	
2	759263.69	3857737.46	734.53	BM11-3	
3	759264.53	3857821.12	735.99	BM11	
4	759281.39	3857766.57	735.25	BM11B	
5	759153.02	3857818.71	736.95	BM12-2	
6	759313.64	3857927.31	735.53	BM11-3	
7	759422.93	3857831.03	743.21	BM11C-1	
8	759257.48	3857606.67	733.68	BM11-4	
9	759436.83	3858057.39	736.01	BM11-4	
10	759535.97	3857767.01	742.52	BM11C-2	
11	759314.26	3857489.42	733.48	BM11-5	
12	759654.38	3857735.59	742.47	BM11C-3	
13	759568.8	3858162.65	737.51	BM11-5	
14	759344.67	3857341.81	732.16	BM11-5	
15	759651.04	3857718.15	742.1	BM11C-4	
16	759221.35	3857823.12	736.85	BM12	
17	759361.05	/ 3857812.7	735.04	BM11C	

SUBMITTED

CHD./VER.

APPROVED APPROVED

RECOMMENDED

PAKHTUNKHWA HIGHWAY AUTHORITY

NATIONAL ENGINEERING SERVICES PAKISTAN (PVT.) LTD.

REV. DATE

CONSTRUCTION OF GRADE SEPERATED INTERSECTION

AT SHAHEED CHOWK TIMERGARA


DATE


MARCH, 2022


TRAVERSE STATIONS


SA-488/102/TD/TS005


DWG NO.














1.1 SPECIFIC TO PROJECT ONLY AND SHOULD BE READ IN CONJUNCTION WITH THE PROJECT SPECIFICATIONS, STRUCTURAL ENGINEERING DRAWINGS, RELEVANT CONTRACT CONDITINS AND ENGINEER'S INSTRUCTIONS.

1.2 ALL DRAWINGS SHALL BE CO-ORDINATED WITH OTHER SPECIALTY DRAWINGS / DETAILS. ANY DISCREPANCY, ERROR OR RECTIFICATION IF REQUIRED, SHALL BE BROUGHT TO THE NOTICE OF THE ENGINEER FOR NECESSARY APPROVAL.

1.3 ALL DIMENSIONS ARE IN MILLIMETRES AND ELEVATIONS IN METRES. UNLESS SPECIFIED OTHERWISE.

1.4 ALL ELEVATIONS SHOWN ON DRAWINGS ARE FINISHED SURFACE LEVELS UNLESS NOTED OTHERWISE.

1.5 ALL EXPOSED CONCRETE CORNERS, EDGES AND ANGLES SHALL CHAMFERED OR FILLETED 20mm x 20mm UNLESS SPECIFIED OTHERWISE.

1.6 THE CONTRACTOR SHALL SUBMIT, COMPLETE METHODOLOGY FOR DIFFERENT WORK ITEMS LIKE EXCAVATION/BACKFILLING, DEWATERING/DRAINAGE, CONCRETING, JOINTS ETC FOR APPROVAL OF ENGINEER.

1.7 ALL EXPOSED SURFACES SHALL HAVE CLASS 1 SURFACE FORM FINISH UNLESS SPECIFIED OTHERWISE.

MATERIALS:

2.1 ALL THE MATERIALS AND WORKMANSHIP SHALL BE ACCORDING TO THE AASHTO SPECIFICATIONS AND ASTM STANDARDS EXCEPT WHERE MODIFIED BELOW, OR IN "PARTICULAR SPECIFICATIONS AND SPECIAL PROVISIONS" OF TENDER DOCUMENTS.

CONCRETE CLASSIFICATION AND STRENGTHS SHALL BE AS PER TABLE GIVEN BELOW:

CONCRETE	CLASS	28 DAYS CYLINDER STRENGTH (psi)
CULVERT (TOP SLAB), BOTTOM SLAB, WALLS, WINGWALL	А3	4000
APPROACH SLAB, CUTOFF WALL	A2	3500
GIRDER	d1	5000
PCC SHOULDER	1: 2: 4	3000
LEAN CONCRETE	1: 4: 8	1500

2.3 REINFORCEMENT

REINFORCING STEEL SHALL BE DEFORMED ROUND BARS OF INTERMEDIATE GRADE (GRADE 60) CONFORMING TO AASHTO M-31 (ASTM A-615) WITH MINIMUM YIELD STRENGTH OF 4,200 Kg/Sq.Cm (60,000 Psi).

CONCRETE COVER:

THE MINIMUM COVER TO REINFORCEMENT SHALL BE AS UNDER UNLESS SPECIFIED OTHERWISE.

TOP SLAB TOP. 40 mm

APPROACH SLAB 50 mm воттом TOP 75 mm

WALLS EARTH SIDE 50 mm OTHER SIDE 40 mm

FOUNDATIONS:

- 4.1 ALL THE EXCAVATION FOR OPEN FOUNDATIONS / BOX CULVERTS SHALL BE SUBJECTED TO INSPECTION BY THE ENGINEER PRIOR TO POURING OF CONCRETE.
- 4.2 BEHIND THE ABUTMENT AND WING WALLS, COMPACTED GRANULAR BACKFILL SHALL BE PLACED IN LAYERS OF THICKNESS APPROPRIATE TO THE COMPACTION EQUIPMENT ENSURING A MINIMUM IN SITU COMPACTION OF 95% MODIFIED PROCTOR.

JOINTS:


5.1 THE CONTRACTOR SHALL SUBMIT COMPLETE LAYOUT AND DETAILS OF ALL CONSTRUCTION JOINTS FOR APPROVAL OF THE ENGINEER.

5.2 CONCRETE IN DECK SLAB SHALL BE PLACED IN FULL WIDTH. NO CONSTRUCTION JOINT SHALL BE PERMITTED. DIAPHRAGMS AND DECK SLAB SHALL BE CAST MONOLITHICALLY. EXCEPT AS SHOWN ON DRAWING AT LOCATION FOR INSTALLATION OF EXPANSION JOINTS.

5.3 CONCRETE FOR THE BARRIERS AND SIDEWALKS SHALL BE PLACED NO SOONER THAN 20 DAYS AFTER PLACING OF CONCRETE.

BAR BENDING SCHEDULE

DETAILED BAR BENDING SCHEDULE SHALL BE PREPARED BY THE CONTRACTOR AND SUBMITTED FOR ENGINEER'S APPROVAL. LAP LENGTHS AND STANDARD HOOKS SHALL BE AS GIVEN BELOW:



TENDER DOCUMENTS, DRAWINGS & CONSTRUCTION DRAWINGS:

7.1 TENDER DRAWINGS ISSUED WITH TENDER DOCUMENTS ARE TO APPRAISE THE BIDDERS OF THE GENERAL NATURE & FAIR IDEA OF THE WORK TO PREPARE BOQ & TENDER DOCUMENTS. ENGINEER SHALL ISSUE THE DETAILED CONSTRUCTION DRAWINGS & SUCH FIELD SKETCHES FROM TIME TO TIME AS NECESSARY FOR THE EASE OF CONSTRUCTION.

7.2 THE CONTRACTOR SHALL CHECK ALL CONSTRUCTION DRAWINGS AND CONTRACT DOCUMENTS CAREFULLY AS SOON AS PRACTICABLE AFTER RECEIPT THERE OF, AND SHALL PROMPTLY ADVICE THE ENGINEER'S REP OF ANY ERRORS OR OMISSIONS THERE IN PRIOR TO START OF ANY CONSTRUCTION ACTIVITIES.

SCAFFOLDING:

ALL SCAFFOLDING SHALL BE DESIGNED BY THE CONTRACTOR & THE TRAFFIC MOVEMENT UNDERNEATH SUCH SCAFFOLDING MAY REMAIN UNOBSTRUCTED.



9. LIST OF SYMBOLS AND ABBREVIATIONS:

воттом () B.H BORE HOLE CONSTRUCTION JOINT C. JT. CENTRELINE CENTER TO CENTER C/C DIAMETER DÍA. EXP. JT. E.F EXPANSION JOINT EACH FACE ELE. F.F FAR FACE GALVANIZED IRON

INTERNAL DIAMETER ID INNER FACE METER NEAR FACE

NATURAL SURFACE LEVEL P.G.L SYM. PROFILE GRADE LEVEL TOP

TH. TYPICAL SKEW ANGLE IN DEGREES

TABLE NO.1

(i) SPLICE LENGTH IN TENSION

(a) TOP BARS

Bar Size	SPLICE LENGTH mm									
Kg/cm ²	#3	#4	#5	#6	#7	#8	#9	#10	#11	
210	710	945	1180	1410	2060	2355	2645	2940	3240	
280	610	820	1020	1225	1780	2040	2995	2550	2805	
350	425	565	705	845	1215	1390	1565	1765	1960	

(b) OTHER BARS

Bar Size	SPLICE LENGTH mm										
Kg/cm²	#3	#4	#5	#6	#7	#8	#9	#10	#11		
210	550	730	905	1085	1590	1815	2035	2265	2490		
280	475	630	790	945	1375	1570	1765	1960	2160		
350	325	435	540	650	935	1070	1205	1360	1505		

(ii) SPLICE LENGTH IN COMPRESSION

SPLICE	LENGT	H (mm	i) IN C	OMPRE	ESSION	l (F)	y=422	OKg/c	m ²)
Bar Size	#3	#4	#5	#6	# 7	#8	#9	#10	#11
Splice Length	300	380	480	575	670	765	860	955	1050


(iii) EMBEDMENT LENGTH IN TENSION

(a) TOP BARS

Bar Size	A STATE OF THE STA	SPLIC	E LEN	IGTH n	nm				
rc Kg/cm²	#3	#4	#5	#6	#7	#8	#9	#10	#11
210	545	730	910	1090	1590	1820	2050	2310	2565
280	475	630	785	945	1360	1555	1755	1975	2190
350	425	565	705	845	1215	1390	1565	1765	1960

Bar Size		SPLI	CE LEI	NGTH I	mm				
Kg/cm ²	#3	#4	#5	#6	#7	#8	#9	#10	#11
210	420	560	700	840	1225	1400	1580	1775	1970
280	365	485	605	725	1045	1195	1350	1520	1685
350	325	435	540	650	935	1070	1205	1360	1505





Т		T	The same		DRAWN	
F			V		SUBMITTED	
					RECOMMENDED	
Ī					CHD./VER.	
ļ	REV.	DATE	DESCRIPTION	APPROVED	APPROVED	

CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA

TITLE	GENERAL	NOTES	FOR
	STRU	CTURES	5

DWG NO. SA-488/102/TD/GNS012 MARCH, 2022

NOT TO BE USED FOR CONSTRUCTION

SHAPE M	NETHOD OF MEASUREMENT OF BENDING DIMENSIONS	TOTAL LENGTH OF BAR (L) MEASURED ALONG CENTERLINE	SKETCH AND DIMENSIONS TO BE GIVEN IN SCHEDULE	SHAPE CODE	METHOD OF MEASUREMENT OF BENDING DIMENSIONS	TOTAL LENGTH OF BAR (L) MEASURED ALONG CENTERLINE	SKETCH AND DIMENSIONS TO BE GIVEN IN SCHEDULE	SHAPE CODE	METHOD OF MEASUREMENT OF BENDING DIMENSIONS	TOTAL LENGTH OF BAR (L) MEASURED ALONG CENTERLINE	SKETCH AND DIMENSIONS TO BE GIVEN IN SCHEDULE	SHAPE CODE	METHOD OF MEASUREMENT OF BENDING DIMENSIONS	paratricular contrata de la companya de la company	SKETCH AND DIMENSIONS TO BE GIVEN IN SCHEDULE
1.	A	A .	Straight	17.		A+B+C Where D is at least 2 diameters	A B C	33.	m	A+0.57B+C	BC	49	R R	2A+2B+C+2D-R-2d	^
2.		А+Н	HC	18.	A P P	A+2B+C+E If angle with horizontal is 45° or less	A B B	34.	- C	A+B+C+D If angle with horizontal is 45° or less		50.		A +B	P
3.		A+2H	'C	19.	E C C C	A+B+C+D+E-R-2d	A D E	35.	R	A+B+C-1/2R-d	<i>y</i>	51.	R m	A+2B+2C-2R-4d	C B
4.		A+B	B	20.	A m	2A+1.14B	M(rd)	38.	D B C	A+B+C If angle with hortzontal is 45° or less	D B S E	52.	m K	A+2B-R-2d	вГА
5.	d A	A+2B	B	21.	⊌ R B	2A+B+20d	A(Ld) B	37.	m R D	A+B+C+D-1½R-3d	B C D	53.	4	A+B+C	A B C
8.	▼ R(standard)	A+B-½R-d	A B	22.	R E D	A+B+C+D+E-2R-4d	B	35.	/E/B/E/D	A+B+C+D+3E If angle with horizontal is 45° or less	A C D	54.		A+B+C+D-1½R-3d	A C
7.	R R O	A+B+C-R-2d	^C	23.	R D	A+2B+C+10#	B	30.		*	\	55.		A+B+C+D+E	B C D E
8,	R O	A+B+C+D+E-2R-4d	B	24.	A	A+lap		40.	R O	A+B+C+D+E+F−½R−d	B C D	56.	C R R R R R R R R R R R R R R R R R R R	A+B+C+D- ½ R−d	c C D
9.	▼ R O	A+B+C-R-2d	A	25.	▼ S R - B	2A+2B+22¢		41.		A+B+C	В	57.		A+B+C+D+E-2½R-3d	\$\$
10.	B U	A+B+C+D-1%R-3d	A C	26.	B O	A+B+0.57C+D-1/2R-2.57d	A B	42.	C	A+28+2C-2R-4d	E B	58.	0 B	A+B+C+D-R+32d	Dy. A B
11.	m R	A+B+C+D+E-R-2d	B C O	27.	y B	2A+B+20≠	2 B	43.	m R	A+2B+2C-2R-4d	B	59.		A+B+C-½R-d	B
12.	S A R	A+B+C+D−½R−d	D_A_B	28.	▼	2A+2B+C+20#	A B C	44.	■ C R	A+28+2C-R-2d	A B C	80.		2(A+B)+C-R-2d	c A
13.		A+B+C+D+E- ½ R-d	€ Å B C D	29.	■ C	A+B+C+10#	A C	45.	D R	A+2(B+C+D)—R-2d	D C	61.	C R P	A+2B+C+D-R-2d	B
14.	R O	2(A+B+C)+D-R-2d		30.	A	*************************************	(h)	46.		2(A+B+C)+D-R-2d	C B A				
15.		(C/B)*3.14*(A+d)+8d Where, B is not greater than A/5. d = dia of bar.	HELIX A = internal dia.(mm) B = pitch of helb(mm) C = overall height(mm)	31.	R O	<u>A+B+</u> C+D−½R−d	A B C	47.		A+B+C+D+E-2R-4d	B D			NOTES: 1- "9" AND "d" ARE THE E 2- "R" IS THE RADIUS OF	NAMETER OF REINFORCEMENTS. BEND IN RADIANS.
16.	B	A+B	B	32.	æ R	2(A+B+C)+D-R-2d	A B C B C B C B C C B C C C C C C C C C	48.	R R	A+B+C−½R−d	8 A				

TENDER DRAWINGS

PAKHTUNKHWA HIGHWAY AUTHORITY


NATIONAL	ENGINEERING	SERVICES	
PAKISTAN	(PVT.) LTD.		

		ELA COLLEGE		DRAWN	
				SUBMITTED	
				RECOMMENDED	
				CHD./VER.	
REV.	DATE	DESCRIPTION	APPROVED	APPROVED	

CONSTRUCTION OF GRADE SEPERATED INTERSECTION
AT SHAHEED CHOWK TIMERGARA

TITLE	REBAR	SHAPE	CODE
-------	-------	-------	------

DATE	
DAIL	DWG NO.
MARCH, 2022	SA-488/102/TD/RS013



-| <u>f |e|^g|h|</u>-


RIGHT BEND DIMENSION(cm)

	SIGN	SIZE
PARTS	90cm	120cm
г	3.5	4.7
a	1.0	1.3
Ь	6.5	8.7
c	4.0	5.3
d	11.5	15.3
е	8.5	11.3
f	7.0	9.3
g	6.0	8.0
h	3.5	4.7
r1	12.5	16.7




LEFT BEND DIMENSION(cm)

	SIGN	SIZE
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
С	4.0	5.3
d	11.5	15.3
е	8,5	11.3
f	7.0	9.3
g	6.0	8.0
h	3.5	4.7
r1	12.5	16.7



(FIRST TO LEFT) DIMENSION(cm)


	SIGN	ISIZE
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
c	3.0	4.0
d	33.0	44.0
е	14.0	18.7
f	8.0	10.7
g	7.0	9.3
h	2.0	2.7
i	3.5	4.7
r1	4.5	6.0



(FIRST TO RIGHT) DIMENSION(cm)

	SIGN SIZE		
PARTS	90cm	120cm	
r	3.5	4.7	
a	1.0	1.3	
b	6.5	8.7	
С	3.0	4.0	
d	33.0	44.0	
8	14.0	18.7	
f	8.0	10.7	
g	7.0	9.3	
h	2.0	2.7	
i	3.5	4.7	
r1	4.5	6.0	


TENDER DRAWINGS NOT TO BE USED FOR CONSTRUCTION



STEEP ASCEND

DIMENSION(cm)


	SIGN SIZE		
PARTS	90cm	120cm	
r	3.5	4.7	
a	1.0	1.3	
b	6.5	8.7	
С	3.5	4.7	
d	23.5	31.3	
е	11.5	15.3	
f	33.0	44.0	



STEEP DESCEND

DIMENSION(cm)


	SIGN SIZE		
PARTS	90cm	120cm	
٢	3.5	4.7	
a	1.0	1.3	
b	6.5	8.7	
С	3.5	4.7	
d	23.5	31.3	
ė	11.5	15.3	
######################################	33.0	44.0	



ROADWAY NARROWS (FROM LEFT)

DIMENSION(cm)

	SIGN SIZE	
PARTS	90cm	120cm
r	3.5	4.7
α	1.0	1,3
ь	6.5	8.7
С	3.5	4.7
d	10.0	13.3
e	14.0	18.7
f	2.5	3.3
g	5.0	6.7



ROADWAY NARROWS DIMENSION(cm)

	SIGN	SIZE
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
С	3.5	4.7
d	10.0	13.3
_ e	14.0	18.7
3	2,5	3.3
V2 .	5.0	6.7

DUAL CARRIAGEWAY STARTS

DIMENSION(cm)

DIME	NOIOI	M(GIII)	
	SIGN SIZE		
PARTS	90cm	120cm	
r	3.5	4.7	
a	1.0	1.3	
b	6.5	8.7	
С	4.5	6.0	
d	15.0	20.0	
е	9.0	12.0	
f	12.0	16.0	
g	9.0	12.0	
h	7.0	9.3	

| <u>h|h | h</u> |

DUAL CARRIAGEWAY ENDS

DIMENSION/

	SIGN SIZE		
PARTS	90cm	120cm	
r	3.5	4.7	
а	1.0	1.3	
b	6.5	8.7	
С	4,0	5.30	
d	15.0	20.0	
е	9,0	12.0	
f	12.0	16.0	
g	9.0	12.0	
h	7.0	9.3	

ENDER DRAWINGS



NATIONAL ENGINEERING SERVICES PAKISTAN (PVT.) LTD.

	(/ // // Mark Mark // //			er installer i de la companya de la
- Janes Constant		TO STATE OF THE ST		DRAWN	
		* 01		SUBMITTED	
				RECOMMENDED	
				CHD./VER.	
REV.	DATE	DESCRIPTION	APPROVED	APPROVED	


CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA

TITLE

ROAD SIGNS (1) (INFORMATORY SIGN)

DATE


DWG NO. SA-488/102/TD/RS014 MARCH, 2022



MINOR ROAD FROM LEFT

DIMENSION(cm)


	Sign	i Size
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
c	3.0	4.0
d	13.5	18.0
е	5.5	7.3
f	15.0	20.0
g	7.0	9.3
h	14.0	18.7
i, a	10.5	14.0



CROSS ROAD AHEAD

DIMENCION(---)


	Sign Size		
PARTS	90cm	120cm	
r	3.5	4,7	
a	1.0	1.3	
ь	6.5	8.7	
С	3.0	4.0	
đ	13.0	17.3	
е	7.0	9.3	
f	10.0	13.3	
g	2.5	3.3	
i	5.0	6.7	



		r		
,				i Aar
				5
			١	-
		$\Rightarrow \setminus$		0
7				٥
	l		/	ام ر

MINOR ROAD FROM RIGHT


	Sign	Sign Size		
PARTS	90cm	120cm		
Г	3.5	4.7		
a	1.0	1.3		
b	6.5	8.7		
С	3.0	4.0		
d	13.5	18.0		
e	5.5	7.3		
f	15.0	20.0		
g	7.0	9.3		
h	14.0	18.7		
1	10.5	14.0		




MINOR ROAD CROSSING WITH AN OFFSET

DIMENSION(cm)

		Sign Size
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
¢	2.5	3.3
d	8.0	10.7
ө	7.5	10.0
f	9.0	12.0



	Sign	Size
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
ь	6.5	8.7
c	2,5	3.3
d	8.0	10.7
е	7.5	10.0
f	9.0	12.0




TENDER DRAWINGS

T- JUNCTION AHEAD


PARTS	Sign	Size
	90cm	120cm
r	3,5	4.7
a	1.0	1.3
b	6.5	8.7
С	3.0	4.0
d	15.5	20.7
е	7.0	9.3
f.	5.0	6.7
g	11.0	14.7

2.5





PARTS	Sign	Size
	90cm	120cm
r	3.5	4.7
а	1.0	1.3
b	6.5	8.7
С	2.5	3.3
d	39.0	52.0
е	27.0	36.0
f	13.0	17.3
g	5.0	6.7




MAIN	N ROAD
(ON	RIGHT
DIMEN	SION(cı

PARTS	Sign Size		
	90cm	120cm	
r	3.5	4.7	
a	1.0	1.3	
b	6.5	8.7	
С	2.5	3.3	
d	39.0	52.0	
е	27.0	36.0	
f	13.0	17.3	
9	5.0	6.7	



MINOR ROAD FROM LEFT DIMENSION(cm)

	Sign	Size
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
С	3.5	4.7
d	33.0	44.0
e	7.0	9.3
f	14.0	18.7
g	15.0	20.0
h	3.0	4.0
i	5.5	7.3



MINOR ROAD FROM RIGHT

		S n	3.0	4.0		
1			5.5	7.3		
-//	18	(re)		DRA	WN	
/	7	//		SUE	BMITTED	
				REC	OMMENDED	
				CHE)./VER.	

APPROVED APPROVED

DESCRIPTION

REV. DATE

CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA

TITLE ROAD SIGNS (2) (INFORMATORY SIGN)


DATE

MARCH, 2022


DWG NO. SA-488/102/TD/RS015



NATIONAL ENGINEERING SERVICES PAKISTAN (PVT.) LTD.



PARTS	Sign Size	
	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
c	2.5	3.3
d	8.0	10.7
е	7.5	10.0
f	9.0	12.0








ROUNDABOUT


DIMENSION(cm)


	Sign Size		
PARTS	90cm		
r	3.5	120	
a	1.0	-	
b	6.5	-	
С	3.0	-	
d	9.0	-	
r1	12.0	-	
r2	16.0	-	
r2	16.0	_	











TWO WAY TRAFFIC

Y-JUNCTION

DIMENSION(om)

	Sign	Size
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
С	3.0	4.0
d	17.0	22.7
е	13.0	17.3
f	7.0	9.3

U-TURN

DIMENSION(cm)

	Sign	Size
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
С	5.5	7.3
d	7.0	9.3
е	5.0	6.7
f	2.5	3.3
g	23.0	30.7
h	7.5	10.0
-1	12.0	16.0

DANGER WARNING

DIMENSION(cm)

	Sign	Size
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
b	6.5	8.7
С	6.5	8.7
d	7.0	9.5

SLOW


DIMENSION(cm)

OTME	TOTOI.	4 (C 111	
	Sign Size		
PARTS	90cm	120cm	
r	3.5	4.7	
а	1.0	1.3	
b	6.5	8.7	
С	6,5	8.7	
d	16.0	21.3	

	Sign	Size
PARTS	90cm	120cm
r	3.5	4.7
a	1.0	1.3
ь	6.5	8.7
c	4.0	8.7
d	9.0	21.3
e	19.0	21.3
f	5.0	21.3
g	3.5	21.3

T27)







ENTRY TO 30KM/H ZONE

END OF SPEED LIMIT IMPOSED

END OF PROHIBITION OF OVFERTAKING

PAKHTUNKHWA HIGHWAY AUTHORITY

NATIONAL ENGINEERING SERVICES PAKISTAN (PVT.) LTD.

andisting or effect		1		DRAWN	
		1/1 %		SUBMITTED	
				RECOMMENDED	
				CHD./VER.	
REV.	DATE	DESCRIPTION	APPROVED	APPROVED	

CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA


TITLE ROAD SIGNS (3) (WARNING SIGN)


DATE


MARCH, 2022


DWG NO. SA-488/102/TD/RS016

NOT TO BE USED FOR CONSTRUCTION










KEEP RIGHT



STRAIGHT OR LEFT ONLY SIGN

d 8.0 10.7

e 9.0 12.0

f 34.0 45.3

g 10.5 14.0

h 23.5 31.3

i 4.5 6.0

r 8.0 10.7

(C6)

IME	NSIOI	V(cm)
	SIGN	SIZE
PARTS	90cm(C4)	120cm(C3)
a	1.0	1.3
b	6.5	8.7

PARTS	SIGN SIZE		
PARIS	90cm(C4)	120cm(C3	
a	1.0	1.3	
ь	6.5	8.7	
c	10.0	13.3	
d	8.0	10.7	
	9.0	12.0	
1.	34.0	45.3	
g	10.5	14.0	
h	23.5	31.3	
. 1	4.5	6.0	
r	8.0	10.7	

STRAIGHT OR RIGHT ONLY SIGN

NO ENTRY

		N(cm) Size	2.0 (2.0 (2.0 (2.0 (2.0 (2.0 (2.0 (2.0 (Sigr	Size
राड	90cm	120cm	PARTS	90cm	120cm
, -	1.0	1.3	•	1.0	1,3
,	4.0	5.3	ь	6.5	8.7
	8.0	10.7	•	5.5	7.3
1	64.0	85.3	d	6.0	8.0
			•	10.0	13.3
			1	25.0	33.3
			g	5.0	6.7
			h	30.0	40.0

DIMI	ENSIC
PARTS	90cm(C1
. 0	1.0
ь	6.5
c	5.5
d	6.0
•	10.0
f	25.0
g	5.0

TURN

1.3

8.7

7.3

8.0

13.3


33.3


6.7

h 30.0 40.0

	SIGN SIZE	
PARTS	90cm(C4)	120cm(C3
a	1.0	1.3
ь	4.0	5.3
c	8.0	10.7
d	9.0	12.0
•	32.0	42.7
1	23.0	30.7
g	4.5	6.0

DIMENSION(cm) 1.0 1.3 b 4.0 5.3 d 9.0 12.0 e 32.0 42.7 f 23.0 30.7






	(7)	-
<u>о</u>	9 8	
	HTV	
	CORROR TAKE	T (400)

SPEED LIMIT (100)


	SIGN	SIZE
PARTS	90cm(C4)	120cm(C3
a	1.0	1.3
ь	6.5	8.7
c	3.0	4.0
d	23.0	30.7
ė	20.0	26.7



NO RIGHT TURN

SPEED LIMIT (120)

	Sign	Size
PARTS	90cm	120cm
a	1.0	1.3
ь	6.5	8.7
c	2.5	3.25
d	5.0	6.5
•	11.25	15.38
f	35.0	47.0
9	40.0	53.5



SPEED LIMIT (60)

	Sign	Size
PARTS	90cm	120cm
a	1.0	1.3
ь	6.5	8.7
c	3.0	4.0
d	23.0	30.7
•	20.0	26.7

MIN. VERTICAL CLEARANCE DIMENSION(cm)

	Sign	Size
PARTS	90cm	120cm
a	1.0	1.3
ь	6,5	8.7
•	13.5	18.0
d	12.5	17.0
	8.5	11.5
1	31.0	41.0
g	24.5	32.5
h	12.5	16.5

MAX. GROSS WEIGHT LIMIT

	Sign	Size
PARTS	90cm	120cm
a	1.0	1.3
ь	6.5	8.67
c	32.0	42.50
d	2.5	3.50
. 0	17.0	22.50
f	1.5	2.0
9	17.0	22.50
h	3.5	4.50
1	10.0	13.50

STOP

DIMENSION(cm)

	Sign	Size
PARTS	90cm	120cm
۵	1.0	1.30
b	37.0	49.5
C	20.0	25.0
d	15.0	20.0
•	36.0	43.0
1	90.0	120.0






,			
	NATIONAL.	ENGINEERING	SERVICES
	11111101111	(PVT.) LTD.	


3		DESCRIPTION	APPROVED	CHD./VER.	
			MANAGAR SANAGAR ANG		
				SUBMITTED	
				DRAWN	


CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA


ı		SIGNS (4) LATORY SIGN)
	DATE	DWG NO.
	MARCH, 2022	SA-488/102/TD/RS017

NOT TO BE USED FOR CONSTRUCTION










SINGLE SIGNS


GI STEEL POST 675x3.2mm 600 (SHOULDER LEVEL) SEE DETAIL 'A'


PAKHTUNKHWA HIGHWAY AUTHORITY



DOUBLE SIGNS

SINGLE SIGNS WITH ADDITIONAL PLATE





PLAN

SECTION

PRECAST CONCRETE FOUNDATION (TYPE-1) DETAIL 'A'

NOTES:-

- 1- ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE.
- 2- POST LENGTH AS SHOWN ARE FOR EXPRESSWAY SIGNS OF 1200mm NOMINAL SIZE. FOR RAMPS, POST LENGTH SHALL BE ADJUSTED ACCORDINGLY.
- 3- PRECAST CONCRETE FOUNDATION BLOCKS SHALL BE CAST USING CLASS "B" CONCRETE.
- 4- SIGN PANELS SHALL BE MADE OF ALUMINUM ALLOY PLATES OF MINIMUM 3mm THICKNESS.
- 5- FOR ALL TRIANGULAR, CIRCULAR SIGNS AND INFORMATION SIGNS OF LESS THEN 1.5m Sq.m AREA, USE INNER DIA 75mm, 3.2mm THICK CIRCULAR GI POST WITH.
- 6— ALL SIGN POSTS SHALL BE PAINTED WITH NON—REFLECTORISED BLACK AND WHITE PAINT STRIPES 300mm WIDE.
- 7- ALL SIGN BACK PANELS SHALL BE PAINTED WITH GRAY ENAMEL PAINT

MARCH, 2022

8- ALL POSTS SHALL BE 300mm SHORT OF SIGN TOP.






PAKISTAN (PVT.) LTD.


		1011		DRAWN	
				SUBMITTED	co
				RECOMMENDED	
				CHD.∕VER.	
REV.	DATE	DESCRIPTION	APPROVED	APPROVED	


CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA

TITLE	TYPICAL PLACEMENT
	OF ROAD SIGNS
DATE	DWG NO.

SA-488/102/TD/RS018







(FOR <60 Km/hr)


(FOR >60 Km/hr)

LANE SELECTION ARROWS - WHITE


ARROWS TYPE-III (DEFLECTION)

TABLE - 1


ROADWAY SPEED	L (mm)	W1	W2	W3	W4	W5
<50 Km/hr	2000	100	100	100	300	100
50-80 Km/hr *	3000	120	120	150	300	100
>120 Km/hr	4000	ERVICES.	200	200	400	100



ADDITIONAL DETAIL FOR MEDIAN AND CARRIAGE WAY



ENTRANCE NOSE DETAIL SCALE 1:300



PAVEMENT MARKING & ROAD STUDS DETAILS

NOTES :-

- 1. ALL DIMENSIONS ARE IN MILLIMETERS.
- 2. AT APPROACHES TO INTERSECTIONS/ROUNDABOUTS, CENTER LINE OR LANE SEPARATION LINE (L1) BECOMES (L2) FOR A LENGTH = 150m AND CONTINUOUS LINE (L3) FOR LAST 50m.
- 3. LENGTH OF STORKE IN (L2) = LENGTH OF GAP IN MATCHING (L1).
- 4. LOCATION OF DIRECTIONAL ARROWS, NOSES AND STOP SIGN SHALL BE PLACED AS DIRECTED BY THE ENGINEER.



(RAISED PROFILE TYPE)

PLAN

REFLECTORISED PAVEMENT STUD

NATIONAL ENGINEERING SERVICES PAKISTAN (PVT.) LTD.

SECTION A-A

,			11/10:		DRAWN	
					SUBMITTED	
					RECOMMENDED	
					CHD./VER.	
	REV.	DATE	DESCRIPTION	APPROVED	APPROVED	

CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK

TIMERGARA


TITLE


PAVEMENT MARKING AND ROAD STUDS


DATE


SA-488/102/TD/PMS019 MARCH, 2022

















ELEVATION ANCHORS ASSEMBLY TYPE NO.1 (BREAKAWAY)







PLAN



ELEVATION ANCHORS ASSEMBLY TYPE NO.2





NOTES

- 1. ALL DIMENSIONS ARE IN MILLIMETERS. UNLESS NOTED OTHERWISE.
- 2. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH DWG. NO. SA-488/102/TD/GR020.)
- 3. THE LAYOUT AND DETAILS SHOWN ON THIS PLAN ARE INDICATIVE ONLY OF THE VARIOUS POSSIBILITIES AVAILABLE FOR THE APPROACH AND TAIL ENDS FOR GUARD RAIL
- 4. IN CASE SOLID ROCK IS ENCOUNTERED, THE POST MAY BE SHORTENED, PROVIDED IT EXTENDS INTO THE SOLID ROCK A MIN. OF 900mm.

PAKHTUNKHWA HIGHWAY AUTHORITY

ELEVATION BURIED POST ANCHOR

> NATIONAL ENGINEERING SERVICES PAKISTAN (PVT.) LTD.

	- /	NE MEDICAL PROPERTY OF THE PRO			
	4	IS DE LO		DRAWN	
				SUBMITTED	
		TAN *		RECOMMENDED	
				CHD./VER.	
REV.	DATE	DESCRIPTION	APPROVED	APPROVED	

CONSTRUCTION OF GRADE SEPERATED INTERSECTION AT SHAHEED CHOWK TIMERGARA


TITLE


TYPICAL GUARD RAIL DETAILS (2)

DATE


DWG NO.

SA-488/102/TD/GR021 MARCH, 2022









TENDER DRAWINGS



PAKHTUNKHWA HIGHWAYS AUTHORITY (PKHA) GOVERNMENT OF KPK



NATIONAL ENGINEERING SERVICES PAKISTAN (PVT.) LTD.

\. \ \(\(\) \\ \(\)		DRAWN	JUNAID	T
		SUBMITTED	INAM ULLAH	Ī
\ \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\		RECOMMENDED		
		CHD./VER.		
DESCRIPTION	APPROVED	ADDROVED		1

CONSTRUCTION OF GRADE SEPERATED INETERSECTON AT SHAHEED CHOWK TIMERGARA

PROJECT

PLAN	&	PROFILE	

SCALE 1:1500

DATE DWG NO.
February 2022 SA-488/TD/P&P 3